

340+ Dixwell, New Haven, CT

80% Affordable (60% AMI or less) and 20% Market

A Mass Timber & Passive House Integrated Design
with Photovoltaics

69 Units Total



340+ Dixwell Project Team:

Architect of Record /Passive House Consultant:

Schadler Selnau Associates, PC
5 Waterville Road Farmington, CT 06032
Paul Selnau, AIA, CPHC ©

Presenter

Design Architect + Mass Timber Consultant:

Gray Organschi Architecture
35 Crown Street New Haven, CT 06510

Structural Engineer:

Odeh Engineers
1223 Mineral Spring Avenue, North
Providence, RI 02904

US Forest Service through 2018
Wood Innovation Grant (WIG)



Owners:

David Cleghorn – H.E.L.P. Development Corp.
Darrell Brooks – Beulah Land Development Corporation
Jeff Spiritos – Spiritos Properties LLC

Presenter



Mechanical & Electrical Engineer:

Acorn Consulting Engineers Inc.
244 Farms Village Road, West Simsbury, CT 06092


Civil Engineer:

John Paul Garcia & Associates, P.C.
190 Fairwood Road, Bethany, CT 06524

Low Income Housing Tax Credit Project through
CHFA, DOH and City of New Haven, CT.
Covid related shortfall impedes closing and
construction start



Structural Strategy



Interior Renderings




Typical unit interior rendering




Main lobby interior rendering

Typical Unit Layouts

Typical one bedroom unit




Typical two bedroom unit



Wall, Ceiling Strategies

Exposed CLT exterior wall



Metal Framed Corridor Walls

Dropped ceiling @ kitchen, hall, & bath

Exposed CLT @ living room & bedroom

Exposed CLT wall in stair


Exposed CLT wall

Dropped ceiling in corridors

Exposed CLT exterior wall



HVAC Strategies



Incremental benefits for mass timber vs light frame

1. **Parts and pieces** – with light frame, there are many more elements to gather and put together
2. **Height**– Light frame can be a maximum of 5 floors over a concrete or steel podium
3. **Site impact** - more deliveries, traffic, trade parking needed with light frame
4. **Crew size** – 20-30 people compared to 6 or so with mass timber
5. **Labor challenges** – greater and greater shortages of labor challenge progress and pricing
6. **Elevator and stair core walls** – typically done in concrete or concrete block
7. **Waste and clutter**– cutting lumber, sheathing, TJI's on site, blocking, and bracing all take space and create safety concerns with waste
8. **Eliminate the steel or concrete podiums**, which are the carbon emitting technologies – not structurally required
9. **Speed** – a) erecting walls, shear walls, bearing walls, ceiling joists, connections take longer than placing glulam/CLT panels
b) need to wait till roof is on to start insulation and gypsum due to water infiltration concerns
10. **Quality** – dimensional lumber is less dimensionally stable
11. **Thermal performance** – wood studs are thermal breaks in an outer wall that diminish wall R value
12. **Safety** – fall and trip hazards, and walking on installed joists are a skill
13. **Fire risk during construction** – Dimensional lumber more susceptible
14. **Insurance costs** – May be higher with light frame due to construction risks (safety and fire) during placement
15. **Durability** – light frame structures are subject to more movement and weather impact
16. **Natural environment** – Light frame buildings require covering all wood with artificial surfaces
17. **Healthfulness** – exposed wood shown to reduce asthma and stress, lowers heart rate and blood pressure, improve concentration

340+ Dixwell Mass Timber VS Light Frame Cost Comparison

NOTE - GENERAL CONTRACTOR ADD ONS - GC, INSURANCE, BOND, FEE ARE REFLECTED PROPORTIONATELY
 NOTE - COST DIFFERENCES IN THE 0% PERCENTAGE COLUMN ARE DUE TO ROUNDING

BUILDING GROSS SF 86,807

CATEGORY	MASS TIMBER (MT) (\$)	LIGHT FRAME (LF) (\$)	MT PERCENTAGE OF LF (%)
GENERAL REQUIREMENTS	678,927	720,541	-5.78%
SITework	885,870	894,752	0%
FOUNDATION	627,196	633,450	0%
MASONRY	124,375	401,891	-69.05%
METALS	380,692	599,767	-36.53%
WOOD STRUCTURE & PLASTICS	4,592,849	2,384,866	92.58%
THERMAL & MOSITURE	2,390,586	2,108,925	0%
DOORS & WINDOWS	983,251	993,056	0%
FINISHES	1,370,747	1,861,678	73.63%
SPECIALTIES	78,395	79,180	0%
EQUIPMENT	237,577	239,948	0%
FURNISHINGS	308,454	311,529	0%
CONVEYING SYSTEMS	502,332	507,341	0%
FIRE PROTECTION	467,385	472,045	0%
PLUMBING	1,037,884	1,048,232	0%
HVAC	1,546,477	1,561,897	0%
ELECTRICAL	1,631,961	1,648,233	0%
SUBTOTAL	17,844,958	16,467,331	108.37%
CONSTRUCTION PERIOD INTEREST (2 MO)	-80,000		-80,000
NET RENT COLLECTION (2 MO)	-20,000		-20,000
SUBTOTAL COST OFFSET	-100,000		-100,000
TOTAL COST WITH OFFSET	17,744,958		
COST/SF	205.57	189.70	15.87
OFFSETTING NET REVENUE	-1.15		-1.15
TOTAL COST/SF	204.42	189.70	14.72

340+ Dixwell



340+ Dixwell Project Overview

Project Location	340 Dixwell Avenue, New Haven, CT
Project Type	Residential Multi-family
Construction	Cross-laminated timber (CLT)
Total Units	57 (Bldg. 340) 12 (Bldg. 316)
Overall SF	65,766 sf (Bldg. 340) 14,047 sf (Bldg. 316)
Number of Stories	4 (Bldg. 340) 4 (Bldg. 316) & Rooftop Terrace
Exterior Wall Insulation Material	Rockwool Comfortboard 80 4" (Bldg. 340) 6" (Bldg. 316)
Slab Insulation	2" Con't EPS (Bldg. 340) 6" Con't EPS (Bldg. 316)




316 Dixwell


340 Dixwell




Mass Timber Systems




DLT
dowel-laminated timber



NLT
nail-laminated timber




GLT
glue-laminated timber



CLT
cross-laminated timber

Mass Timber Building Assembly



Wufi Modeling:

340 Dixwell



Name					
4" Conc Slab -2" EPS					
Thermal resistance [hr ft² °F/Btu]: 9.62 / 9.62 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	EPS (heat cond.: 0.04 W/mK - density: 1)		0.0181	2	9.2
2	Concrete		0.7933	4	0.42

5 ply clt Roof -12" Polyisocyanurate (Average)					
Thermal resistance [hr ft² °F/Btu]: 77.792 / 77.792 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	Polyisocyanurate Insulation		0.0139	12	72.114
2	5-ply cross-laminated panel		0.0693	4.724	5.678

3 ply CLT Wall - 4" Rockwool Confortboard 80					
Thermal resistance [hr ft² °F/Btu]: 18.835 / 18.835 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	(de-Valued) Rockwool Confortboard 80		0.0236	4	14.1
2	INTELLO (according to German approve		1.3867	0.039	0.002
3	3-ply cross-laminated panel		0.0693	3.937	4.732

5 ply CLT Wall - 4" Rockwool Confortboard 80					
Thermal resistance [hr ft² °F/Btu]: 18.835 / 18.835 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	(de-Valued) Rockwool Confortboard 80		0.0236	4	14.1
2	INTELLO (according to German approve		1.3867	0.039	0.002
3	5-ply cross-laminated panel		0.0693	3.937	4.732

R-value

9.62
Slab

77.792
Roof

18.835
3 Ply
Ext. Wall

18.835
5 Ply
Ext. Wall

316 Dixwell



R-value

28.045
Slab

77.792
Roof

26.093
3 Ply
Ext. Wall

26.093
5 Ply
Ext. Wall




Name					
4" Conc Slab -6" EPS					
Thermal resistance [hr ft² °F/Btu]: 28.045 / 28.045 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	EPS (heat cond.: 0.04 W/mK - density: 1)		0.0181	6	27.624
2	Concrete		0.7933	4	0.42

5 ply clt Roof -12" Polyisocyanurate (Average)					
Thermal resistance [hr ft² °F/Btu]: 77.792 / 77.792 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	Polyisocyanurate Insulation		0.0139	12	72.114
2	5-ply cross-laminated panel		0.0693	4.724	5.678

3 ply CLT Wall - 6" Rockwool Confortboard 80					
Thermal resistance [hr ft² °F/Btu]: 26.093 / 26.093 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	(de-Valued) Rockwool Confortboard 80		0.02341	6	21.358
2	INTELLO (according to German approve		1.3867	3.9E-2	0.002
3	3-ply cross-laminated panel		0.0693	3.937	4.732

5 ply CLT Wall - 6" Rockwool Confortboard 80					
Thermal resistance [hr ft² °F/Btu]: 26.093 / 26.093 (EN ISO 6946 / homogenous layers)					
Nr.	Material / Layer (from outside to inside)	Color	λ [Btu/hr ft °F]	Thickness [in]	R [hr ft² °F/Btu]
1	(de-Valued) Rockwool Confortboard 80		0.02341	6	21.358
2	INTELLO (according to German approve		1.3867	3.9E-2	0.002
3	5-ply cross-laminated panel		0.0693	3.937	4.732



316 Dixwell: Foundation & Slab Detail





① TYP. DIXWELL STREET FDN DETAIL @ 3 PLY
1 1/2" = 1'-0"

Wood Framed PH vs CLT Framed PH: Exterior Wall & Floor Detail


*wood framed
construction-
passive house*




*cross laminated
timber
construction-
passive house*








340 Dixwell: Roof Detail




1 TYP. EXTERIOR WALL DETAIL @ ROOF--4 inch insulation (BLDG. 340)
3" = 1'-0"



Typical Window Details



Exterior Detailing for thermal bridges: North Facade



North Cowl Thermal Bridge Calculation:

30 FT Vertical
(2 Sides)
8 FT Horizontal
(2 Sides)

Total = 76 FT

$$912(.072) = 65.664$$

Linear thermal bridges

Nr	Name	Linear thermal transmittance [Btu/hr ft °F]	Length [ft]	Attachment
1	Apt above parking: #1 on A011	0.198	126.324	Ambient
2	North Facade Part Plan 1: #1/ A-307A	0.072	76	Ambient
3	North Facade Section @ Soffit: #10 /A307A	0.008	333.25	Ambient
4	Entry Door Sill Detail: A002 #1	0.261	27	Ambient
5	Grid C at Mech Rm: #1 / A006	0.16	47.74	Ambient

Boundary Conditions		T (F)	Surface Film Resist. (R-Value)
Floor	Ex.	68	0.74
			0.57
			0.97
Outdoor Ambient		Ex. 14	0.23/0.45
Ground		Ex. 41	0



*Enter values from THERM into yellow cells

2D model	U (btu/hr.sf.F)	dT (F)	L (in)	ULdT (btu/hr.ft)	error (%)
Interior	0.0593	54	84.13	22.45	4.78%
Exterior	0.0415	54	120.05	22.42	4.78%

Component	U (btu/hr.sf.F)	dT (F)	L (in)	ULdT (btu/hr.ft)	error (%)
Component A	Interior 0.0490	54	84.13	18.55	0.00%
WALL-4INCH, 100 mm	Exterior 0.049	54.00	84.13	18.55	0.00%
Component B	Interior			0.00	0.00%
N/A	Exterior 0.0000	0.00	0.00	0.00	0.00%

Psi	PsidT (btu/hr.ft)	dT (F)	Psi (btu/hr.ft.F)	Psi for WUFI (btu/hr.ft.F)
Interior	3.90	54.00	0.072	0.072
Exterior	3.87	54.00	0.072	

Exterior Detailing for thermal bridges: Typical door at grade




Entry Door Thermal Bridge Calculation:

7 total exterior doors
(Bldg. 340)

Total Length= 27 feet

$$324(.261) = 84.564$$



2D model		U (btu/hr.sf.F)	dT (F)	L (in)	ULdT (btu/hr.ft)	error (%)
	Interior	0.1038	54	75.19	35.12	4.97%
	Exterior	0.0164	54	476.83	35.19	4.97%


Component		U (btu/hr.sf.F)	dT (F)	L (in)	ULdT (btu/hr.ft)	error (%)
Component A	Interior	0.1419	54	11.98	7.65	0.00%
Glass Door	Exterior	0.142	54.00	11.98	7.65	0.00%
Component B	Interior	0.0609	27	72	9.87	0.00%
Slab	Exterior	0.0609	27.00	72.00	9.87	0.00%
Component C	Exterior	0.0491	54	16.00	3.54	0.00%
WALL-4INCH	Exterior	0.049	54.00	16.00	3.54	0.00%

Psi		PsidT (btu/hr.ft)	dT (F)	Psi (btu/hr.ft.F)	Psi for WUFI (btu/hr.ft.F)
Interior	14.07	54.00	0.261	0.261	
Exterior	14.14	54.00	0.262		


Exterior Detailing for thermal bridges: Balcony detail

Balcony Thermal Bridge Calculation:

31 total balconies Length 10 ft 9 in
 129 inches x 31 balconies = 3999
 $3999 (0.008) = 31.992$



- ACCOYA DECKBOARDS (1/8" GAP)
- ICE AND WATER SHIELD
- PT SLEEPERS
- GLULAM DECK STRUCTURE
- GLULAM OR STEEL ANGLE LEDGER



2D model		U (btu/hr.sf.F)	dT (F)	L (in)	ULdT (btu/hr.ft)	error (%)
	Interior	0.0224	54	135.67	13.68	3.42%
	Exterior	0.022	54	138.25	13.69	3.42%

Component		U (btu/hr.sf.F)	dT (F)	L (in)	ULdT (btu/hr.ft)	error (%)
Component A	Interior	0.0483	54	60.99	13.26	0.00%
WALL-4INCH, 100 mm	Exterior	0.048	54.00	60.99	13.26	0.00%
Component B	Interior				0.00	0.00%
N/A	Exterior	0.0000	0.00	0.00	0.00	0.00%

Psi	PsidT (btu/hr.ft)	dT (F)	Psi (btu/hr.ft.F)	Psi for WUFI (btu/hr.ft.F)
Interior	0.42	54.00	0.008	0.008
Exterior	0.43	54.00	0.008	

Flooring Assembly Analysis At Soffit

FLOORING ASSEMBLY ABOVE SOFFITS

- 4.7mm LVT
- 1" USG Levelrock
- Vapor retarder (20 perm)
- 5/8" Plywood
- 1 1/2" x 3 1/2" sleepers
- CLT floor panel
- 24" Cellulose
- Aquarock Soffit



OCCUPIED SPACE

OCCUPIED SPACE

TYPICAL FLOORING ASSEMBLY

- 4.7mm LVT
- 50mm USG Levelrock
- 25mm Geniemat FF25
- CLT floor panel

UN-OCCUPIED SPACE



Case	Mold Criterion	Rot Criterion	Initial Dry Out Time
Case 1: Proposed Floor Assembly	Fail	Pass, dry out issues in plywood though	Fail
Case 9: Gyp Screed	Pass	Pass, dry out issues in ply	Fail
Case 10: No Intello	Pass	Pass	Pass

Ventilation/Mechanical Systems



Swegon ERV

ERV-1

1885 CFM

ERV-2

2380 CFM



Variable Refrigerant Flow

VRF-1A

25.7/11.55 (IEER/EER)

VRF-1B

22.3/11.15 (IEER/EER)

VRF-2A

26.9/12.3 (IEER/EER)

VRF-2B

22.3/11.15 (IEER/EER)



Rinnai
SENSEI



Tankless Water Heater

Super High Efficiency (Condensing)

Rinnai -CU199i

Up to 97% thermal efficiency

Certifications: AHRI, ANSI Z21.10.3,
CSA 4.3, and Energy Star®



Fujitsu

Airstage VR-II

EER (95F): 10.90

IEER: 19.60

SCHE: 25.20




Quest 70 Dehumidifier

150 CFM


120 Volts

Typical Apartment Building: Ventilation/Mechanical Systems


Typical Unit Mechanical Plan



Mechanical Partial Upper Plan
On demand central water heating




Mechanical Partial Roof Plan 1




Renewable Energy

Source energy





35,000 kWh/yr Onsite Utilization from PV energy covering 36.46% of building electric usage

Source energy



145,000 kWh/yr Onsite Utilization from PV energy covering 26.16% of building electric usage



180,000 kWh/yr Onsite Utilization from PV energy covering 27.68% of Total electric usage

Carbon Emissions for 340+ Dixwell Project



Volume of wood products used:
2,468 cubic meters (87,156 cubic feet)



Avoided greenhouse gas emissions:
738 metric tons of carbon dioxide



Carbon stored in wood:
1906 metric tons of carbon dioxide



Total potential carbon benefit:
2644 metric tons of carbon dioxide



U.S. and Canadian forests grow this much wood in:
7 minutes

Equivalent to: _____






559 cars off the road for a year



Energy to operate 279 homes for a year

In conclusion...



Key Points:

1. Increasing **popularity in CLT incorporating** net-zero design strategies and embodied carbon. Used in a range of **affordable multifamily** housing projects because of its structural diversity.
2. Both traditional and CLT wood-frame structures meet the performance and net-zero goals for the affordable multifamily type, but in different ways.
3. Each construction type has its own unique challenge when designing to highly energy efficient structures.
4. Innovations in wood framing design techniques and products enhancing the energy efficiency in affordable multifamily projects

Thank you!